
CONSTRUCTION AGGREGATE INC. VILLAGE CENTER ESTATES, PHASE 2 NORTH YARMOUTH, MAINE

LOCATION MAP




<u>TITLE</u>	DWG NO
COVER SHEET	
GENERAL NOTES, LEGEND, AND ABBREVIATIONS	C-100
EXISTING CONDITIONS PLAN	C-101
SUBDIVISION PLAN	C-102
SITE LAYOUT AND UTILITIES PLAN	C-103
GRADING AND EROSION CONTROL PLAN	C-104
WILDLIFE LANE PLAN AND PROFILE - STA 0+00 TO STA 8+50	C-200
WILDLIFE LANE PLAN AND PROFILE - STA 8+50 TO STA 16+29.52	C-201
SPILLWAY DRIVE PLAN AND PROFILE	C-202
UNDERDRAINED SOIL FILTER PLANS AND SECTION	C-203
UNDERDRAINED SOIL FILTER PLANS AND SECTION	C-204
STORMWATER MANAGEMENT AREA GRAVEL WETLAND	C-205
EROSION CONTROL NOTES AND DETAILS	C-300
SECTIONS AND DETAILS	C-301
SECTIONS AND DETAILS	C-302
SECTIONS AND DETAILS	C-303
SECTIONS AND DETAILS	C-304
STORMWATER MANAGEMENT PLAN - PRE-DEVELOPMENT CONDITIONS	D-100
STORMWATER MANAGEMENT PLAN - POST-DEVELOPMENT CONDITIONS	D-101



ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE

4 Blanchard Road, PO Box 85A, Cumberland Center, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com



GENERAL NOTES:

- 1. BASE MAP DERIVED FROM SURVEY PERFORMED BY WAYNE T. WOOD & CO. ENTITLED "PLAN OF LAND OF SMITH ON WALNUT HILL ROAD IN NORTH YARMOUTH, MAINE FOR FREDERICK CHERNER, 4 PINEWOOD DR. ~CUMBERLAND CTR, ME 04021", DATED JUNE, 2018.
- 2. EXISTING ZONING LINE AND GROUNDWATER PROTECTION OVERLAY ZONE DIGITIZED FROM TOWN OF NORTH YARMOUTH ZONING MAP.
- 3. ALL SITE AND CONSTRUCTION ACTIVITIES SHALL BE IN COMPLIANCE WITH MEDEP BEST MANAGEMENT PRACTICES AND EXISTING FEDERAL, STATE, AND LOCAL PERMITS AND PERMITTING REQUIREMENTS FOR THE SITE.
- 4. SOILS INFORMATION FROM HIGH INTENSITY SOIL SURVEY COMPLETED BY MARK HAMPTON ASSOCIATES ON DECEMBER 3, 2019.
- 5. THE EXISTING CONTOURS SHOWN IN THE PHASE I AREA ARE FROM DESIGN DRAWINGS BY SME, DATED AUGUST 29, 2018. THE EXISTING CONTOURS SHOWN IN THE PHASE II AREA ARE TAKEN FROM LIDAR AS AVAILABLE FROM MAINE GIS DATA CATALOG.

SURVEYOR'S NOTES

- OWNERS OF RECORD ARE GAIL S. BRUNS, CINDY A. CHERNER AND J. WHITMAN SMITH BY DEED OF DISTRIBUTION OF SIDNEY D. SMITH RECORDED IN THE CUMBERLAND COUNTY REGISTRY OF DEEDS IN BOOK 12,863 ON PAGE 144 AND NORMAN L. & NELSON L. SMITH BY DEED OF DISTRIBUTION OF NORMAN L. SMITH RECORDED IN THE SAID REGISTRY OF DEEDS BOOK 32,519 PAGE 82.
- 2. ALL BEARINGS ARE REFERENCED TO MAGNETIC NORTH OF THE YEAR 1983 PER THE PLAN IN SURVEYOR'S PLAN REFERENCE NOTES #9 AND ARE CALCULATED FROM ANGLES OF AN ACTUAL ON THE GROUND SURVEY.
- 3. THE SUBJECT PARCEL IS SHOWN ON THE TOWN OF NORTH YARMOUTH, MAINE TAX MAP 7 AS LOT 34.
- 4. THE EXISTING CONTOURS SHOWN ARE TAKEN FROM LIDAR AS AVAILABLE FROM MAINE GIS DATA CATALOG.
- 5. WETLANDS SHOWN ARE AS DELINEATED BY SWEET ASSOCIATES ON A PLAN DATED JUNE 10, 2016. ADDITIONAL WETLANDS SHOWN ARE AS DELINEATED BY MARK HAMPTON ASSOCIATES ON JULY 1, 2018.
- 6. THE RICHARD BASTON PROPERTY MAY HAVE AN EASEMENT OR RIGHT OF WAY ACROSS THIS PROPERTY OVER THE SECTION OF THIS PARCEL LABELED AS THE "OSGOOD/ DOLLOFF LOT" FOR THE PURPOSES OF ACCESSING THE BASTON LOT FOR WOOD HARVESTING ACTIVITIES.

SURVEYOR'S PLAN REFERENCE NOTES

- 1. "PLAN OF LAND ON MEMORIAL HIGHWAY IN NORTH YARMOUTH, MAINE FOR FREDERICK CHERNER" DATED SEPTEMBER 2017 BY WAYNE T. WOOD & CO.
- 2. "GUIDI FLASH HOLDINGS ~ STONE POST SUBDIVISION ~ ROUTE 115 ~ NORTH YARMOUTH, MAINE" DATED MARCH 2016 BY SEVEE & MAHER ENGINEERING RECORDED IN PLAN BOOK 216 PAGE 384.
- 3. "CONDOMINIUM PLAT WALNUT HILL CONDOMINIUM 2 WALNUT HILL ROAD, NORTH YARMOUTH, MAINE MADE FOR PIPER, LLC" DATED APRIL 15, 2015 BY OWEN HASKELL, INC. RECORDED IN PLAN BOOK 215 PAGE 138.
- 4. "PLAN OF LAND FOR THOMAS AND SARE CURTIS" DATED OCTOBER 2013 BY COLONIAL SURVEYING COMPANY, LLC RECORDED IN PLAN BOOK 215 PAGE 31.
- 5. "UPDATE TO A STANDARD BOUNDARY SURVEY SHOWING LAND OF REBECCA L. SWIGGETT FOR THE TRUST FOR PUBLIC LAND GREELY ROAD EXTENSION & PLEASANT VALLEY ROAD, CUMBERLAND & NORTH YARMOUTH, MAINE" DATED AUGUST 26, 2013 REVISED 6/3/2014.
- 6. "RIGHT OF WAY MAP STATE AID HIGHWAY NOS. 2 & 3 (ROUTES 9 & 115) NORTH YARMOUTH, CUMBERLAND COUNTY" DATED JUNE 2004.
- 7. "STANDARD BOUNDARY SURVEY FOR RICHARD & HELEN KNIGHT, GREELY ROAD EXTENSION, CUMBERLAND / NORTH YARMOUTH, MAINE" DATED FEB 1, 1996 REVISED THRU 7/15/96 RECORDED IN PLAN BOOK 196 PAGE 395.
- 8. "STANDARD BOUNDARY SURVEY ON ROUTE 115 IN NORTH YARMOUTH, MAINE FOR NELLIE LEIGHTON & PAUL & BETTY KAY TURINA" DATED 1/26/1989 BY DANIEL T.C. LAPOINT.
- 9. "STANDARD BOUNDARY SURVEY PLAN OF LAND ON ROUTE 115 IN NORTH YARMOUTH, MAINE FOR NORMAN L. SMITH, SIDNEY D. SMITH" DATED 4/17/1987 BY DANIEL T. C. LAPOINT.

EXISTING GROUND OR GRADE

ON CENTER

OUTSIDE DIAMETER

10. "PLAN OF LAND FOR PAUL CLARK, ROUTE 115, NORTH YARMOUTH, ME" DATED 7/10/1978 BY C. R. STORER, INC. RECORDED IN PLAN BOOK 120 PAGE 30.

GENERAL SITE NOTES:

- 1. EXCAVATE AND STOCKPILE ON-SITE TOPSOIL. TOPSOIL IS TO REMAIN THE PROPERTY OF THE OWNER DURING CONSTRUCTION, AND SHALL NOT BE REMOVED FROM THE SITE. AFTER FINAL LOAM AND SEED EXCESS TOPSOIL SHALL BE REMOVED FROM SITE BY CONTRACTOR.
- 2. PAVEMENT EDGES SHALL BE TRUE TO LINE. SAWCUT EXISTING PAVEMENT IN SMOOTH STRAIGHT LINE WHERE NEW PAVEMENT JOINS, PROVIDE TACK COAT LAYER AS SPECIFIED.
- 3. PROVIDE TRAFFIC CONTROL SIGNAGE AND STRIPING AS SHOWN AND IN ACCORDANCE WITH U.S.D.O.T. MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MOST RECENT VERSION).
- 4. HORIZONTAL DATUM: NAD83, WEST, FT. VERTICAL DATUM: NAVD 88.

GRADING NOTES:

- 1. ADD 4" LOAM, SEED AND MULCH TO DISTURBED AREAS UNLESS OTHERWISE NOTED, PROVIDE EROSION CONTROL MESH ON ALL SLOPES STEEPER THAN 3:1, AND ALONG DITCH CHANNELS.
- 2. MAINTAIN TEMPORARY EROSION CONTROL MEASURES FOR THE FULL DURATION OF CONSTRUCTION. INSPECT WEEKLY AND AFTER EACH STORM AND REPAIR AS NEEDED, REMOVE SEDIMENTS FROM THE SITE, PLACE IN AREA OF LOW EROSION POTENTIAL, AND STABILIZE WITH SEED AND MULCH.
- 3. PLACE TEMPORARY SOIL STABILIZATION WITHIN 7 DAYS OF INITIAL DISTURBANCE. PLACE PERMANENT SOIL STABILIZATION WITHIN 7 DAYS OF FINAL GRADING.

UTILITY NOTES:

- 1. THE ACCURACY AND COMPLETENESS OF SUBSURFACE INFORMATION IS NOT GUARANTEED. VERIFY SITE CONDITIONS INCLUDING TEST PITS FOR LOCATIONS AND INVERTS OF UTILITIES AND REPORT ANY DISCREPANCIES TO THE ENGINEER PRIOR TO PROCEEDING WITH THAT PORTION OF THE WORK.
- 2. COORDINATE WORK ON UTILITY LINES OR WITHIN ROAD RIGHT-OF-WAY WITH THE UTILITY COMPANIES AND TOWN ROAD DEPARTMENT AND MEDOT.
- 3. ALL PIPING AND DRAINAGE STRUCTURES SHALL BE INSTALLED IN ACCORDANCE WITH THE TOWN OF NORTH YARMOUTH MUNICIPAL STANDARDS.

DIG SAFE NOTES:

PRIOR TO EXCAVATION, VERIFY THE UNDERGROUND UTILITIES, PIPES, STRUCTURES AND FACILITIES. PROVIDE THE FOLLOWING MINIMUM MEASURES:


- 1. PRE-MARK THE BOUNDARIES OF PLANNED EXCAVATION WITH WHITE PAINT, FLAGS OR STAKES, SO UTILITY CREWS KNOW WHERE TO MARK THEIR LINES.
- 2. CALL DIG SAFE, AT 811, AT LEAST THREE BUSINESS DAYS BUT NO MORE THAN 30 CALENDAR DAYS BEFORE STARTING WORK. DO NOT ASSUME SOMEONE ELSE WILL MAKE THE CALL.
- 3. IF BLASTING, NOTIFY DIG SAFE AT LEAST ONE BUSINESS DAY IN ADVANCE.
- 4. WAIT THREE BUSINESS DAYS FOR LINES TO BE LOCATED AND MARKED WITH COLOR-CODED PAINT, FLAGS OR STAKES. NOTE THE COLOR OF THE MARKS AND THE TYPE OF UTILITIES THEY INDICATE. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.
- 5. CONTACT THE LANDOWNER AND OTHER "NON-MEMBER" UTILITIES (WATER, SEWER, GAS, ETC.). FOR THEM TO MARK THE LOCATIONS OF THEIR UNDERGROUND FACILITIES. TRANSFER THESE MARKS TO THE AS-BUILT DRAWINGS.
- 6. RE-NOTIFY DIG SAFE AND THE NON-MEMBER UTILITIES IF THE DIGGING, DRILLING OR BLASTING DOES NOT OCCUR WITHIN 30 CALENDAR DAYS, OR IF THE MARKS ARE LOST DUE TO WEATHER CONDITIONS, SITE WORK ACTIVITY OR ANY OTHER REASON.
- 7. HAND DIG WITHIN 18 INCHES IN ANY DIRECTION OF ANY UNDERGROUND LINE UNTIL THE LINE IS EXPOSED. MECHANICAL METHODS MAY BE USED FOR INITIAL SITE PENETRATION, SUCH AS REMOVAL OF PAVEMENT OR ROCK.
- 8. DIG SAFE REQUIREMENTS ARE IN ADDITION TO TOWN, CITY, AND/OR STATE DOT STREET OPENING PERMIT REQUIREMENTS.
- 9. FOR COMPLETE DIG SAFE REQUIREMENTS, CALL THE PUC OR VISIT THEIR WEBSITE.
- 10. IF YOU DAMAGE, DISLOCATE OR DISTURB ANY UNDERGROUND UTILITY LINE, IMMEDIATELY NOTIFY THE AFFECTED UTILITY. IF DAMAGE CREATES SAFETY CONCERNS, CALL THE FIRE DEPARTMENT AND TAKE IMMEDIATE STEPS TO SAFEGUARD HEALTH AND PROPERTY.
- 11. ANY TIME AN UNDERGROUND LINE IS DAMAGED OR DISTURBED OR IF LINES ARE IMPROPERLY MARKED, YOU MUST FILE AN INCIDENT REPORT WITH THE P.U.C. FOR AN INCIDENT REPORT FORM VISIT WWW.STATE.ME.US/MPUC OR CALL THE

PROPERTY LINE SETBACK **EASEMENT** _____ IRON PIPE STONE POST EDGE OF PAVEMENT **EDGE OF GRAVEL** WALKING PATH CONTOUR _____100 _____ SPOT GRADE FENCE STORM DRAIN CULVERT UNDERDRAIN CATCH BASIN UTILITY POLE 0 - UGU — UNDERGROUND UTILITY ———— UGU ———— TRANSFORMER WATER LINE **HYDRANT** SIGN RIPRAP TREELINE TEST PIT ₩ 🕀 WETLAND NO-CUT BUFFER ZONING BOUNDARY GROUNDWATER PROTECTION OVERLAY BOUNDARY RESIDENTIAL SHORELAND ZONING 100' WELL EXCLUSION ZONE \searrow POTENTIAL SEPTIC BED **EROSION CONTROL LEGEND**


LEGEND

PROPOSED

EXISTING



	DPD	12/2020	REVISED PER STAFF COMMENTS
	DPD	10/2020	ISSUED FOR TOWN AND MEDEP PERMIT REVIEW
REV.	BY	DATE	STATUS
	•		



CONSTRUCTION AGGREGATE INC. VILLAGE CENTER ESTATES, PHASE 2 NORTH YARMOUTH, MAINE

GENERAL NOTES, LEGEND, AND ADDDE\/TATIONC

DESIGN BY: JTR
DRAWN BY: SJM
DATE: 1/2020
CHECKED BY: BDP
LMN: NONE
CTB: SME-STD
C-100

TYPICAL ABBREVIATIONS:


ASPHALT COATED CMP

ASBESTOS CEMENT PIPE


	AC	ACRE	ELEC	ELECTRIC		
	AGG	AGGREGATE	EL	ELEVATION	PC	POINT OF CURVE
	ALUM	ALUMINUM	ELB	ELBOW	PD	PERIMETER DRAIN
	APPD	APPROVED	EOP	EDGE OF PAVEMENT	PI	POINT OF INTERSECTION
	APPROX	APPROXIMATE	EOUIP	EQUIPMENT	PIV	
	ARMH		~ -	•		POST INDICATOR VALVE
		AIR RELEASE MANHOLE	EST	ESTIMATED	PT	POINT OF TANGENT
	ASB	ASBESTOS	EXC	EXCAVATE	PERF	PERFORATED
	ASP	ASPHALT	EXIST	EXISTING	PP	POWER POLE
	AUTO	AUTOMATIC			PSI	POUNDS PER SQUARE INCH
	AUX	AUXILIARY	FI	FIELD INLET	PVC	POLYVINYL CHLORIDE
	AVE	AVENUE	FG	FINISH GRADE	PVMT	PAVEMENT
	AZ	AZIMUTH	FBRGL	FIBERGLASS	1 1111	TAVENENT
			FDN	FOUNDATION		
		DIT	FLEX	FLEXIBLE	QTY	QUANTITY
	BCCMP	BITUMINOUS COATED CMP				
	BM	BENCH MARK	FLG	FLANGE	RCP	REINFORCED CONCRETE PIPE
	BIT	BITUMINOUS	FLR	FLOOR	ROW	RIGHT OF WAY
	BLDG	BUILDING	FPS	FEET PER SECOND	RAD	RADIUS
	BOT	BOTTOM	FT OR '	FEET		
	BRG	BEARING	FTG	FOOTING	REQD	REQUIRED
	BV			. 00.10	RT	RIGHT
	ΒV	BALL VALVE	GA	GAUGE	RTE	ROUTE
	CP	CATCH BACINI	GAL			
	CB CEN	CATCH BASIN		GALLON	S	SLOPE
		CENTER	GALV	GALVANIZED	SCH	SCHEDULE
	CEM LIN	CEMENT LINED	GPD	GALLONS PER DAY	SF	SQUARE FEET
	CMP	CORRUGATED METAL PIPE	GPM	GALLONS PER MINUTE	SHT	SHEET
	CO	CLEAN OUT			SMH	SANITARY MANHOLE
(CF	CUBIC FEET	HDPE	HIGH DENSITY POLYETHYLENE	ST	STREET
(CFS	CUBIC FEET PER SECOND	HORIZ	HORIZONTAL	STA	
	CI	CAST IRON	HP	HORSEPOWER		STATION
	CL	CLASS	HYD	HYDRANT	SY	SQUARE YARD
	CONC	CONCRETE		2.0	TAN	TANGENT
			ID	INSIDE DIAMETER	TDH	TOTAL DYNAMIC HEAD
	CONST	CONSTRUCTION	IN OR "	INCHES	TEMP	TEMPORARY
	CONTR	CONTRACTOR			TYP	
(CS	CURB STOP	INV	INVERT	117	TYPICAL
(CTR	CENTER	INV EL	INVERT ELEVATION	UD	UNDERDRAIN
(CU	COPPER				
(CY	CUBIC YARD	LB	POUND	V	VOLTS
	.	00210 171112	LC	LEACHATE COLLECTION	VA TEE	VALVE ANCHORING TEE
	D	DEGREE OF CURVE	LD	LEAK DETECTION	VERT	VERTICAL
	DBL	DOUBLE	LF	LINEAR FEET	· =· · ·	VERTICALE.
	DEG OR °	DEGREE	LOC	LOCATION		
	DEPT	DEPARTMENT			WG	WATER GATE
	DI		LT	LEACHATE TRANSPORT	W/	WITH
-		DUCTILE IRON			W/O	WITHOUT
	DIA OR	DIAMETER	MH	MANHOLE	11/0	WITHOUT
I	DIM	DIMENSION	MJ	MECHANICAL JOINT	VD	VARR
	DIST	DISTANCE	MATL	MATERIAL	YD	YARD
ı	DN	DOWN	MAX	MAXIMUM		
1	DR	DRAIN	MFR	MANUFACTURE		
	DWG		MIN	MINIMUM		
'	DWG	DRAWING	MISC	MISCELLANEOUS		
			MON	MONUMENT		
				NOT IN THE CO		
			NITC	NOT IN THIS CONTRACT		

NOT TO SCALE NOW OR FORMERLY

NO OR # NUMBER



ver/OFS\Ben Grover\Village Center Estates Phase 2\Acad\Plans\BASE.dwg, 12/17/2020 12:44:57 PM., jr



18. MAINTENANCE OF TRAILHEAD PARKING WILL BE BY THE TOWN OF NORTH YARMOUTH. ANY ADDITIONAL

CENTER ESTATES HOME OWNERS ASSOCIATION (PHASE 1 AND 2).

EMERGENCY SITUATIONS.

PARKING OR TRAILHEAD IMPROVEMENTS WILL BE SUBJECT TO REVIEW AND APPROVAL BY THE VILLAGE

19. TOWN PUBLIC WORKS STAFF MAY ACCESS STORMWATER FACILITY AREAS BY ESTABLISHED EASEMENTS IN

_MN: SUBD

CTB: SME-STD

C-102

4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021

Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com

JOB NO. 18295.01 DWG FILE BASE

InserverICFSIBen GroverIVillage Center Estates Phase 2/AcadIPlansIBASE.dwg, 12/17/2020 12:45:40 PM. jrl

"STANDARD BOUNDARY SURVEY PLAN OF LAND ON ROUTE 115 IN NORTH YARMOUTH, MAINE FOR NORMAN L. SMITH,

"PLAN OF LAND FOR PAUL CLARK, ROUTE 115, NORTH YARMOUTH, ME" DATED 7/10/1978 BY C. R. STORER, INC.

SIDNEY D. SMITH" DATED 4/17/1987 BY DANIEL T. C. LAPOINT.


RECORDED IN PLAN BOOK 120 PAGE 30.


WATER SUPPLY:

SEWER SERVICE:


PUBLIC WATER

SEPTIC SYSTEMS (SEE ZONING NOTE 4)







erverICFSIBen GroverIVillage Center Estates Phase 2/Acad/PlansiBASE.dwg, 12/22/2020 1:51:45 PM,




InserverICFSIBen GroverIVillage Center Estates Phase 2\AcadiPlans\BASE.dwg, 12/28/2020 9:




InserverICFSIBen GroverIVIIIage Center Estates Phase 2/AcadIPIansIBASE.dwg, 12/28/2020 9:47:57 AM. jri



Weenaal/PENBan Grount//illane Center Estates Bhase 2) Anaal Dansi BASE Aum 19798/2001 10-15-6



	DPD	12/2020	REVISED PER STAFF COMMENTS
	DPD	10/2020	ISSUED FOR TOWN AND MEDEP PERMIT REVIEW
REV.	BY	DATE	STATUS



CONSTRUCTION AGGREGATE INC.
VILLAGE CENTER ESTATES, PHASE 2
NORTH YARMOUTH, MAINE

UNDERDRAINED SOIL FILTER PLANS AND SECTIONS

DESIGN BY: JTR
DRAWN BY: JRL
DATE: 10/2020

CHECKED BY: BDP

LMN: PLAN-PROF

CTB: SME-STD


C-203


SME _	
SEVEE & MAHER ENGINEERS	
NMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIA	4

ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANC
4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021
Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com


JOB NO. 18295.01 DWG FILE BASE

\\nserver\CFS\Ben Grover\Village Center Estates Phase 2\Acad\Plan






UNDERDRAINED SOIL FILTER #8 SECTION



	DPD	12/2020	REVISED PER STAFF COMMENTS
	DPD	10/2020	ISSUED FOR TOWN AND MEDEP PERMIT REVIEW
RE\/	RY	DATE	STATUS



CONSTRUCTION AGGREGATE INC. VILLAGE CENTER ESTATES, PHASE 2 NORTH YARMOUTH, MAINE

UNDERDRAINED SOIL FILTER PLANS AND SECTIONS

SME SEVEE & MAHER


DESIGN BY: JTR DRAWN BY: JRL DATE: 10/2020 **ENGINEERS** CHECKED BY: BDP


ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com

JOB NO. 18295.01 DWG FILE BASE

CTB: SME-STD C-204

LMN: PLAN-PROF






OUTLET CONTROL STRUCTURE NOTES:

THE CONTRACTOR SHALL PROVIDE SUBMITTALS TO THE ENGINEER FOR APPROVAL. SUBMITTALS SHALL INCLUDE BUT NOT LIMITED TO THE FOLLOWING:

PRODUCT DATA: SUBMIT PRODUCT DATA FOR ALL MATERIALS USED ON THE JOB FOR REVIEW FOR LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH INFORMATION GIVEN AND DESIGN CONCEPT EXPRESSED IN CONTRACT DOCUMENTS.

SHOP DRAWINGS: SUBMIT FOR REVIEW SHOP DRAWINGS OF ALL PRECAST UNITS. MANUFACTURER'S INFORMATION SHALL BE SUBMITTED FOR JOINT SEALANTS AND WATERPROOFING. MANUFACTURE SHALL PROVIDE ANTI-FLOTATION DESIGN SHOP DRAWINGS AND CALCULATIONS, INCLUDING ANY EXTENDED BASE SLABS AS NECESSARY, FOR PROPOSED MANHOLES. MANUFACTURER SHALL ASSUME GROUNDWATER LEVELS EQUAL TOP OF GROUND ELEVATIONS AND PROVIDE FOR A 1.2 FACTOR OF SAFETY AGAINST FLOTATION.

GRAVEL WETLAND OUTLET CONTROL STRUCTURE



NOTES:

- WETLAND SOIL TO BE MANUFACTURED USING COMPOST, SAND AND SOME FINE SOIL. SOIL SHALL CONTAIN GREATER THAN 15% ORGANIC MATTER. CLAY CONTENT OF THE SOIL SHALL BE LESS THAN 15%. SUBMIT TESTS OF MATERIALS MEETING THE ABOVE.
- 2. PEA GRAVEL TO MEET MDOT SPECIFICATION 703.27 UNDERDRAIN TYPE C AND SHALL MEET THE COARSE GRAVEL SPEC ON C-201.
- 3. SEED GRAVEL WETLAND WITH "NEW ENGLAND WET MIX" FROM NEW ENGLAND WETLAND PLANTS. APPLICATION RATE 1LB/2500 SQ FT (18LBS/ACRE)

GRAVEL WETLAND SECTION

	DPD	12/2020	REVISED PER STAFF COMMENTS	
	DPD	10/2020	ISSUED FOR TOWN AND MEDEP PERMIT REVIEW	
REV.	BY	DATE	STATUS	-
THE A PARTY OF THE	DANIEL DIFFIN 11841	TANK TOWN	CONSTRUCTION AGGREGA VILLAGE CENTER ESTATES, NORTH YARMOUTH, MA	PHASE 2 AINE
Ville	CAMED	AMILIA.	STORMWATER MANAGEMEN	NT AREA
*****	WALL	mir.	GRAVEL WETLAND	
			SME 🌰	DESIGN BY: JTR
				DRAWN BY: JRL
			SEVEE & MAHER ENGINEERS	DATE: 10/2020

ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE

4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com

JOB NO. 18295.01 DWG FILE BASE

CHECKED BY: BDP

LMN: PLAN-PROF

C-205

CTB: SME-STD

InserverICFSIBen GroverIVillage Center Estates Phase 2\Acad\Plans\BASE.dwg, 12/22/2020 11:33:22 A

A. GENERAL

- 1. All soil erosion and sediment control will be done in accordance with: (1) the Maine Erosion and Sediment Control Handbook: Best Management Practices, Maine Department of Environmental Protection (MEDEP), October 2016.
- 2. The site Contractor (to be determined) will be responsible for the inspection and repair/replacement/maintenance of all erosion control measures, disturbed areas, material storage areas, and vehicle access points until all disturbed areas are stabilized.
- 3. Disturbed areas will be permanently stabilized within 7 days of final grading. Disturbed areas not to be worked upon within 14 days of disturbance will be temporarily stabilized within 7 days of the disturbance.
- 4. In all areas, removal of trees, bushes and other vegetation, as well as disturbance of topsoil will be kept to a minimum while allowing proper site operations.
- 5. Any suitable topsoil will be stripped and stockpiled for reuse as directed by the Owner. Topsoil will be stockpiled in a manner such that natural drainage is not obstructed and no off-site sediment damage will result. In any event, stockpiles will not be located within 100 feet of wetlands and will be at least 50 feet upgradient of the stockpile's perimeter silt fence. The sideslopes of the topsoil stockpile will not exceed 2:1. Silt fence will be installed around the perimeter of all topsoil stockpiles. Topsoil stockpiles will be surrounded with siltation fencing and will be temporarily seeded with Aroostook rye, annual or perennial ryegrass within 7 days of formation, or temporarily mulched.
- 6. Winter excavation and earthwork will be completed so as to minimize exposed areas while satisfactorily completing the project. Limit exposed areas to those areas in which work is to occur during the following 15 days and that can be mulched in one day. All areas will be considered denuded until the subbase gravel is installed in roadway areas or the areas of future loam and seed have been loamed, seeded, and mulched.

Install any added measures necessary to control erosion/sedimentation. The particular measure used will be dependent upon site conditions, the size of the area to be protected, and weather conditions.

To minimize areas without erosion control protection, continuation of earthwork operations on additional areas will not begin until the exposed soil surface on the area being worked has been stabilized.

B. TEMPORARY MEASURES

1. STABILIZED CONSTRUCTION ENTRANCE/EXIT

A crushed stone stabilized construction entrance/exit will be placed at any point of vehicular access to the site, in accordance with the detail shown on this sheet.

2. SILT FENCE

- a. Silt fence will be installed prior to all construction activity, where soil disturbance may result in erosion. Silt fence will be erected at locations shown on the plans and/or downgradient of all construction activity.
- b. Silt fences will be removed when they have served their useful purpose, but not before the upgradient areas have been permanently stabilized.
- c. Silt fences will be inspected immediately after each rainfall and at least daily during prolonged rainfall. They will be inspected if there are any signs of erosion or sedimentation below them. Any required repairs will be made immediately. If there are signs of undercutting at the center or the edges, or impounding of large volumes of water behind them, they will be replaced with a temporary crushed stone check
- d. Sediment deposits will be removed after each storm event if significant build-up has occurred or if deposits exceed half the height of the barrier.
- 3. STONE CHECK DAMS

Stone check dams will be installed in grass-lined swales and ditches during construction. Remove stone check dams when they have served their useful purpose, but not before upgradient areas have been permanently stabilized.

- 4. EROSION CONTROL MIX SEDIMENT BARRIER
- a. Where approved, erosion control mix sediment barriers may be used as a substitute for silt fence. See the details in this drawing set for specifications.
- b. Rock Filter Berms: To provide more filtering capacity or to act as a velocity check dam, a berm's center can be composed of clean crushed rock ranging in size from the french drain stone to riprap.
- 5. TEMPORARY SEEDING

Stabilize disturbed areas that will not be brought to final grade and reduce problems associated with mud and dust production from exposed soil surface during construction with temporary vegetation.

6. TEMPORARY MULCHING

Use temporary mulch in the following locations and/or circumstances:

- In sensitive areas (within 100 feet of streams, wetlands and in lake watersheds) temporary mulch will be applied within 7 days of exposing spill or prior to any storm event.
- Apply temporary mulch within 14 days of disturbance or prior to any storm event in all other areas
- Areas which have been temporarily or permanently seeded will be mulched immediately following seeding.
- Areas which cannot be seeded within the growing season will be mulched for over-winter protection and the area will be seeded at the beginning of the growing season.
- Mulch can be used in conjunction with tree, shrub, vine, and ground cover
- Mulch anchoring will be used on slopes greater than 5 percent in late fall (past October 15), and over-winter (October 15 - April 15).

The following materials may be used for temporary mulch:

- a. Hay or Straw material shall be air-dried, free of seeds and coarse material. Apply 2 bales/1,000 sf or 1.5 to 2 tons/acre to cover 90% of ground surface.
- b. Erosion Control Mix: It can be used as a stand-alone reinforcement: on slopes 2 horizontal to 1 vertical or less;
- on frozen ground or forested areas; and
- at the edge of gravel parking areas and areas under construction.
- c. Erosion control mix alone is not suitable:
- on slopes with groundwater seepage;
- at low points with concentrated flows and in gullies; • at the bottom of steep perimeter slopes exceeding 100 feet in INMTth;
- below culvert outlet aprons; and around catch basins and closed storm systems.
- d. Chemical Mulches and Soil Binders: Wide ranges of synthetic spray-on materials are marketed to protect the soil surface. These are emulsions that are mixed with water and applied to the soil. They may be used alone, but most often are used to hold wood fiber, hydro-mulches or straw to the soil surface.

- e. Erosion Control Blankets and Mats: Mats are manufactured combinations of mulch and netting designed to retain soil moisture and modify soil temperature. During the growing season (April 15 to October 15) use mats indicated on drawings or North American Green (NAG) S75 (or mulch and netting) on:
- the base of grassed waterways;
- steep slopes (15 percent or greater); and
- any disturbed soil within 100 feet of lakes, streams, or wetlands.

During the late fall and winter (October 15 to April 15) use heavy grade mats indicated on drawings for NAG SC250 on all areas noted above plus use lighter grade mats NAG S75 (or mulch and netting) on:

 sideslopes of grassed waterways; and moderate slopes (between 8 and 15 percent).

C. TEMPORARY DUST CONTROL

To prevent the blowing and movement of dust from exposed soil surfaces, and reduce the presence of dust, use water or calcium chloride to control dusting by preserving the moisture level in the road surface materials.

D. CONSTRUCTION DE-WATERING

- 1. Water from construction de-watering operations shall be cleaned of sediment before reaching wetlands, water bodies, streams or site boundaries. Utilize temporary sediment I. Housekeeping basins, erosion control soil filter berms backed by staked hay bales, A Dirt Bag 55" sediment filter bag by ACF Environmental, or other approved Best Management Practices (BMP's).
- 2. In sensitive areas near streams or ponds, discharge the water from the de-watering operation into a temporary sediment basin created by a surrounding filter berm of uncompacted erosion control mix immediately backed by staked hay bales (see the site details). Locate the temporary sediment basin at lease 100 feet from the nearest water body, such that the filtered water will flow through undisturbed vegetated soil areas prior to reaching the water body or property line.
- E. PERMANENT MEASURES
- 1. Riprapped Aprons: All storm drain pipe outlets and the inlet and outlet of culverts will have riprap aprons to protect against scour and deterioration.
- 2. Topsoil, Seed, and Mulch: All areas disturbed during construction, but not subject to other restoration (paving, riprap, etc.) will be loamed, limed, fertilized, seeded, and

Seeded Preparation: Use stockpiled materials spread to the depths shown on the plans, if available. Approved topsoil substitutes may be used. Grade the site as needed.

a. Seeding will be completed by August 15 of each year. Late season seeding may be done between August 15 and October 15. Areas not seeded or which do not obtain satisfactory growth by October 15, will be seeded with Aroostook Rye or mulched. After November 1, or the first killing frost, disturbed areas will be seeded at double the specified application rates, mulched, and anchored.

PERMANENT SEEDING SPECIFICATIONS

Mixture:	Roadside (lbs/acre)	Lawn (lbs/acre)
Kentucky Bluegrass	20	55
White Clover	5	0
Creeping Red Fescue	20	55
Perennial Ryegrass	5	15

- b. Mulch in accordance with specifications for temporary mulching.
- c. If permanent vegetated stabilization cannot be established due to the season of the year, all exposed and disturbed areas not to undergo further disturbance are to have dormant seeding applied and be temporarily mulched to protect the site.
- 3. Ditches and Channels: All ditches on-site will be lined with North American Green S75 erosion control mesh (or an approved equal) upon installation of loam and seed.
- WINTER CONSTRUCTION AND STABILIZATION
- 1. Natural Resource Protection: During winter construction, a double-row of sediment barriers (i.e., silt fence backed with hay bales or erosion control mix) will be placed between any natural resource and the disturbed area. Projects crossing the natural resource will be protected a minimum distance of 100 feet on either side from the
- 2. Sediment Barriers: During frozen conditions, sediment barriers may consist of erosion control mix berms or any other recognized sediment barriers as frozen soil prevents the proper installation of hay bales or silt fences.

3. Mulching:

- All areas will be considered to be denuded until seeded and mulched. Hay and straw mulch will be applied at a rate of twice the normal accepted rate.
- Mulch will not be spread on top of snow.
- After each day of final grading, the area will be properly stabilized with anchored hay or straw or erosion control matting.
- Between the dates of November 1 and April 15, all mulch will be anchored by either mulch netting, emulsion chemical, tracking or wood cellulose fiber.
- 5. Soil Stockpiling: Stockpiles of soil or subsoil will be mulched for over-winter protection with hay or straw at twice the normal rate or with a 4-inch layer of erosion control mix. This will be done within 24 hours of stocking and re-established prior to any rainfall or snowfall. Any soil stockpiles shall not be placed (even covered with mulch) within 100 feet from any natural resources.
- 6. Seeding: Dormant seeding may be placed prior to the placement of mulch or erosion control blankets. If dormant seeding is used for the site, all disturbed areas will receive 4 inches of loam and seed at an application rate of three times the rate for permanent seeding. All areas seeded during the winter will be inspected in the spring for adequate catch. All areas insufficiently vegetated (less than 75 percent catch) will be revegetated by replacing loam, seed, and mulch.

If dormant seeding is not used for the site, all disturbed areas will be revegetated in the spring.

- 7. Maintenance: Maintenance measures will be applied as needed during the entire construction season. After each rainfall, snow storm, or period of thawing and runoff, and at least once a week, the site Contractor will perform a visual inspection of all installed erosion control measures and perform repairs as needed to ensure their continuous function.
- 8. Identified repairs will be started no later than the end of the net work day and be completed within seven (7) calendar days.

Following the temporary and/or final seeding and mulching, the Contractor will, in the spring, inspect and repair any damages and/or bare spots. An established vegetative cover means a minimum of 85 to 90 percent of areas vegetated with vigorous growth.

- G. OVER-WINTER CONSTRUCTION EROSION CONTROL MEASURES
- Stabilization of Disturbed Soil: By October 15, all disturbed soils on areas having a slope less than 15 percent will be seeded and mulched. If the Contractor fails to stabilize these soils by this date, then the Contractor shall stabilize the soil for late fall and winter, by using either temporary seeding or mulching.

- 2. Stabilization of Disturbed Slopes: All slopes to be vegetated will be completed by October 15. The Owner will consider any area having a grade greater than 15 percent (6.5H:1V) to be a slope. Slopes not vegetated by October 15 will receive one of the following actions to stabilize the slope for late fall and winter:
- a. Stabilize the soil with temporary vegetation and erosion control mesh.
- b. Stabilize the slope with erosion control mix. c. Stabilize the slope with stone riprap.
- 3. Stabilization of Ditches and Channels: All stone-lined ditches and channels to be used to convey runoff through the winter will be constructed and stabilized by November 15. Grass-lined ditches and channels will be complete by September 15. Grass-lined ditches not stabilized by September 15 shall be lined with either sod or riprap.

. MAINTENANCE PLAN

1. Routine Maintenance: Inspection will be performed as outlined in the project's Erosion Control Plan. Inspection will be by a qualified person during wet weather to ensure that the facility performs as intended. Inspection priorities will include checking erosion controls for accumulation of sediments.

- 1. Spill prevention. Controls must be used to prevent pollutants from being discharged from materials on site, including storage practices to minimize exposure of the materials to stormwater, and appropriate spill prevention, containment, and response planning and implementation.
- 2. Groundwater protection. During construction, liquid petroleum products and other hazardous materials with the potential to contaminate groundwater may not be stored or handled in areas of the site draining to an infiltration area. An "infiltration area" is any area of the site that by design or as a result of soils, topography and other relevant factors accumulates runoff that infiltrates into the soil. Dikes, berms, sumps, and other forms of secondary containment that prevent discharge to groundwater may be used to isolate portions of the site for the purposes of storage and handling of these materials.
- 3. Fugitive sediment and dust. Actions must be taken to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil may not be used for dust control. If off-site tracking occurs roadways should be swept immediately and no loss once a week and prior to significant storm events.
- 4. Debris and other materials. Litter, construction debris, and chemicals exposed to stormwater must be prevented from becoming a pollutant source.
- 5. Trench or foundation de-watering. Trench de-watering is the removal of water from trenches, foundations, coffer dams, ponds, and other areas within the construction area that retain water after excavation. In most cases the collected water is heavily silted and hinders correct and safe construction practices. The collected water must be removed from the ponded area, either through gravity or pumping, and must be spread through natural wooded buffers or removed to areas that are specifically designed to collect the maximum amount of sediment possible, like a cofferdam sedimentation basin. Avoid allowing the water to flow over disturbed areas of the site. Equivalent measures may be taken if approved by the department.
- 6. Authorized Non-stormwater discharges. Identify and prevent contamination by non-stormwater discharges. Where allowed non-stormwater discharges exist, they must be identified and steps should be taken to ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge. Authorized non-stormwater discharges are:
- (a) Discharges from firefighting activity;
- (b) Fire hydrant flushings;
- (c) Vehicle washwater if detergents are not used and washing is limited to the exterior of vehicles (engine, undercarriage and transmission washing is prohibited);
- (d) Dust control runoff in accordance with permit conditions and Appendix (C)(3);
- (e) Routine external building washdown, not including surface paint removal, that does not involve detergents;
- (f) Pavement washwater (where spills/leaks of toxic or hazardous materials have not occurred, unless all spilled material had been removed) if detergents are not used;
- (g) Uncontaminated air conditioning or compressor condensate;
- (h) Uncontaminated groundwater or spring water;
- (i) Foundation or footer drain-water where flows are not contaminated; (j) Uncontaminated excavation dewatering (see requirements in Appendix C(5));
- (k) Potable water sources including waterline flushings; and
- (I) Landscape irrigation.
- 7. Unauthorized non-stormwater discharges. The Department's approval under this Chapter does not authorize a discharge that is mixed with a source of non-stormwater, other than those discharges in compliance with Appendix C (6). Specifically, the Department's approval does not authorize discharges of the following:
- (a) Wastewater from the washout or cleanout of concrete, stucco, paint, form release oils, curing compounds or other construction materials;
- (b) Fuels, oils or other pollutants used in vehicle and equipment operation and
- (c) Soaps, solvents, or detergents used in vehicle and equipment washing; and
- (d) Toxic or hazardous substances from a spill or other release.

In general, the expected sequence of construction for each phase is provided below. Construction is proposed to start in and end in 2019.


8. Additional requirements. Additional requirements may be applied on a site-specific basis.

- Mobilization
- Install temporary erosion control measures Clearing and grubbing
- Site Grading
- Install road base, pavement, curbs and sidewalks
- Site stabilization, pavement, loam and seed,


CONSTRUCTION SPECIFICATIONS

1. STONE SIZE - 2" TO 3" STONE OR RECLAIMED OR RECYCLED

- CONCRETE, OR EQUIVALENT.
- 3. LENGTH AS EFFECTIVE, BUT NOT LESS THAN 50 FEET.
- 4. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 5. WIDTH 10 FEET MINIMUM, OR NOT LESS THAN FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.
- MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC REPAIR AND TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.



STABILIZED CONSTRUCTION ENTRANCE/EXIT





NOTES:

- 1. EROSION CONTROL MIX CAN BE MANUFACTURED ON OR OFF THE SITE. IT MUST CONSIST PRIMARILY OF ORGANIC MATERIAL SEPARATED AT THE POINT OF GENERATION, AND MAY INCLUDE: SHREDDED BARK, STUMP GRINDINGS, COMPOSTED BARK, OR FLUME GRIT AND FRAGMENTED WOOD GENERATED FROM WATER-FLUME LOG HANDLING SYSTEMS. WOOD CHIPS, GROUND CONSTRUCTION DEBRIS, REPROCESSED WOOD PRODUCTS OR BARK CHIPS WILL NOT BE ACCEPTABLE AS THE ORGANIC COMPONENT OF THE MIX.
- EROSION CONTROL MIX SHALL CONTAIN A WELL-GRADED MIXTURE OF PARTICLE SIZES AND MAY CONTAIN ROCKS LESS THAN 4" IN DIAMETER. EROSION CONTROL MIX MUST BE FREE OF REFUSE, PHYSICAL CONTAMINANTS, AND MATERIAL TOXIC TO PLANT GROWTH. THE MIX COMPOSITION SHALL MEET THE FOLLOWING STANDARDS:
- A. ORGANIC MATERIAL: BETWEEN 20% 100% (DRY WEIGHT BASIS) B. PARTICLE SIZE: BY WEIGHT, 100% PASSING 6" SCREEN, 70-85% PASSING 0.75" SCREEN
- C. THE ORGANIC PORTION NEEDS TO BE FIBROUS AND ELONGATED. D. LARGE PORTIONS OF SILTS, CLAYS OR FINE SANDS ARE NOT ACCEPTABLE IN THE MIX.


WHERE A PREVIOUS STAND-ALONE FROSION CONTROL MIX APPLICATION HAS FAILED


- E. SOLUBLE SALTS CONTENT SHALL BE LESS THAN 4.0 MMHOS/CM. F. PH: 5.0 - 8.0
- ON SLOPES LESS THAN 5% OR AT THE BOTTOM OF SLOPES 2:1 OR LESS UP TO 20 FEET LONG, THE BARRIER MUST CONFORM TO THE ABOVE DIMENSIONS. ON THE LONGER OR STEEPER SLOPES, THE BARRIER SHOULD BE WIDER TO ACCOMMODATE THE ADDITIONAL FLOW.
- 3. THE BARRIER MUST BE PLACED ALONG A RELATIVELY LEVEL ELEVATION. IT MAY BE NECESSARY TO CUT TALL GRASSES OR WOODY VEGETATION TO AVOID CREATING VOIDS AND BRIDGES THAT WOULD ENABLE FINES TO WASH UNDER THE BARRIER THROUGH THE GRASS BLADES OR PLANT
- 4. LOCATIONS WHERE OTHER BMP'S SHOULD BE USED:
- A. AT LOW POINTS OF CONCENTRATED FLOW B. BELOW CULVERT OUTLET APRONS
- D. AT THE BOTTOM OF STEEP PERIMETER SLOPES THAT ARE MORE THAN 50 FEET FROM TOP TO BOTTOM (LARGE UPGRADIENT WATERSHED E. AROUND CATCH BASINS AND CLOSED STORM DRAIN SYSTEMS.
- 5. THE EROSION CONTROL MIX BARRIERS SHOULD BE INSPECTED REGULARLY AND AFTER EACH LARGE RAINFALL. REPAIR ALL DAMAGED SECTIONS F BERM IMMEDIATELY BY REPLACING OR ADDING ADDITIONAL MATERIAL PLACED ON THE BERM TO THE DESIRED HEIGHT AND WIDTH. 6. IT MAY BE NECESSARY TO REINFORCE THE BARRIER WITH SILT FENCE OR STONE CHECK DAMS IF THERE ARE SIGNS OF UNDERCUTTING OR THE
- IMPOUNDMENT OF LARGE VOLUMES OF WATER.
- 7. SEDIMENT DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE BARRIER. 8. REPLACE SECTIONS OF BERM THAT DECOMPOSE, BECOME CLOGGED WITH SEDIMENT OR OTHERWISE BECOME INEFFECTIVE. THE BARRIER SHOULD BE RESHAPED AS NEEDED
- 9. EROSION CONTROL MIX BARRIERS CAN BE LEFT IN PLACE AFTER CONSTRUCTION, ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER BARRIER IS NO LONGER REQUIRED SHOULD BE SPREAD TO CONFORM TO THE EXISTING GRADE AND BE SEEDED AND MULCHED. WOODY VEGETATION CAN BE PLANTED INTO THE BARRIERS, OR THEY CAN BE OVER-SEEDED WITH LEGUMES. IF THE BARRIER NEEDS TO BE REMOVED, IT CAN BE SPREAD





SURFACE DRAINAGE SEDIMENT CONTROL





NOTE:
USE AT ALL NEWLY CONSTRUCTED GRASS LINED DITCHES AS AN EROSION CONTROL MEASURE AND WHERE OTHERWISE NOTED

DPD | 12/2020 | REVISED PER STAFF COMMENTS DPD | 10/2020 | ISSUED FOR TOWN AND MEDEP REVIEW REV. BY DATE STATUS CONSTRUCTION AGGREGATE INC. VILLAGE CENTER ESTATES, PHASE 2

BARRIER OR SILT FENCE FOR SLOPE

PROTECTION.

EROSION CONTROL NOTES AND DETAILS

NORTH YARMOUTH, MAINE

DESIGN BY: JTR **ENGINEERS** ENVIRONMENTAL • CIVIL • GEOTECHNICAL • WATER • COMPLIANCE 4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021 Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com

JOB NO. 18295.00 DWG FILE DETAILS

DRAWN BY: SJM DATE: 1/2020 CHECKED BY: BDP MN: NONE CTB: SME-STD


C-300

and landscaping


J. CONSTRUCTION SEQUENCE

 Install site utilities Construct gravel wetland, level spreader, and underdrained soil filters

> ON PLANS. STONE CHECK DAM




\\nservenCFS\Ben Grover\Village Center Estates Phase 2\Acad\Plans\\DETAILS.dwg, 1215/2020 1.45:43 PM,




 $\overline{1}$. HMA = HOT MIX ASPHALT. MDOT = MAINE DEPARTMENT OF TRANSPORTATION.

ALL COURSE THICKNESSES AFTER FINAL COMPACTION. SCHEDULE OF SURFACE FINISHES




SEE CMP CO. STANDARD TRENCH FOR BACKFILL MATERIAL REQUIREMENTS. DIRECT BURY CABLES EXCEPT UNDER PAVED AREAS. PROVIDE SCH. 40 PVC CONDUIT UNDER PAVED AREAS, EXTEND CONDUIT 5' BEYOND EDGE OF PAVEMENT.


UNDERGROUND UTILITY TRENCH SECTION





NOTE: CONCRETE PAD AND INSTALLATION PER CMP STANDARDS TYPICAL TRANSFORMER EASEMENT LAYOUT




PAVEMENT STRIPING










CATCH BASIN

CATCH BASIN AND FIELD INLET NOTES

THE CONTRACTOR SHALL PROVIDE SUBMITTALS TO THE ENGINEER FOR APPROVAL. SUBMITTALS SHALL INCLUDE BUT NOT LIMITED TO THE FOLLOWING:

PRODUCT DATA: SUBMIT PRODUCT DATA FOR ALL MATERIALS USED ON THE JOB FOR REVIEW FOR LIMITED PURPOSE OF CHECKING FOR CONFORMANCE WITH INFORMATION GIVEN AND DESIGN CONCEPT EXPRESSED IN CONTRACT DOCUMENTS

SHOP DRAWINGS: SUBMIT FOR REVIEW SHOP DRAWINGS OF ALL PRECAST UNITS. MANUFACTURER'S INFORMATION SHALL BE SUBMITTED FOR JOINT SEALANTS AND WATERPROOFING. MANUFACTURE SHALL PROVIDE ANTI-FLOTATION DESIGN SHOP DRAWINGS AND CALCULATIONS, INCLUDING ANY EXTENDED BASE SLABS AS NECESSARY, FOR PROPOSED MANHOLES. MANUFACTURER SHALL ASSUME GROUNDWATER LEVELS EQUAL TOP OF GROUND ELEVATIONS AND PROVIDE FOR A 1.2 FACTOR OF SAFETY AGAINST FLOTATION.



4 Blanchard Road, PO Box 85A, Cumberland, Maine 04021


Phone 207.829.5016 • Fax 207.829.5692 • smemaine.com

JOB NO. 18295.00 DWG FILE DETAILS

LMN: NONE

CTB: SME-STD

C-302



CONSTRUCTION SEQUENCE: THE SOIL FILTER MEDIA AND VEGETATION MUST NOT BE INSTALLED UNTIL THE AREA THAT DRAINS TO THE FILTER HAS BEEN PERMANENTLY STABILIZED WITH PAVEMENT OR OTHER STRUCTURE, 90% VEGETATION COVER, OR OTHER PERMANENT STABILIZATION UNLESS THE RUNOFF FROM THE CONTRIBUTING DRAINAGE AREA IS DIVERTED AROUND THE FILTER UNTIL STABILIZATION IS COMPLETE.

COMPACTION OF SOIL FILTER: FILTER SOIL MEDIA AND UNDERDRAIN BEDDING MATERIAL MUST BE COMPACTED TO BETWEEN 90% AND 92% STANDARD PROCTOR.

CONSTRUCTION OVERSIGHT: INSPECTION BY A PROFESSIONAL ENGINEER FAMILIAR WITH CONSTRUCTION REQUIREMENTS OF OF UNDERDRAINED SOIL FILTERS WILL OCCUR AT A MINIMUM:


- AFTER THE PRELIMINARY CONSTRUCTION OF THE FILTER GRADES AND ONCE THE UNDERDRAIN PIPES ARE INSTALLED BUT NOT BACKFILLED,
- AFTER THE DRAINAGE LAYER IS CONSTRUCTED AND PRIOR TO THE INSTALLATION OF THE FILTER MEDIA,
- AFTER THE FILTER MEDIA HAS BEEN INSTALLED AND SEEDED.
- AFTER ONE YEAR TO INSPECT HEALTH OF THE VEGETATION AND MAKE CORRECTIONS, AND
- ALL THE MATERIAL USED FOR THE CONSTRUCTION OF THE FILTER BASIN MUST BE CONFIRMED AS SUITABLE BY THE DESIGN ENGINEER. TESTING MUST BE DONE BY A CERTIFIED LABORATORY TO SHOW THAT THEY ARE PASSING DEP SPECIFICATIONS.
- WITHIN 30 DAYS OF COMPLETION OF THE UNDERDRAINED FILTER BASIN, THE APPLICANT MUST SUBMIT A LOG OF INSPECTION REPORTS DETAILING THE ITEMS INSPECTED, PHOTOS TAKEN, AND THE DATES OF EACH INSPECTION TO THE BUREAU OF LAND RESOURCES FOR REVIEW.

TESTING AND SUBMITTALS: THE CONTRACTOR SHALL IDENTIFY THE LOCATION OF THE SOURCE OF EACH COMPONENT OF THE FILTER MEDIA. ALL RESULTS OF FIELD AND LABORATORY TESTING SHALL BE SUBMITTED TO THE PROJECT ENGINEER FOR CONFIRMATION. THE CONTRACTOR SHALL:


- SELECT SAMPLES OF EACH TYPE OF MATERIAL TO BE BLENDED FOR THE MIXED FILTER MEDIA AND SAMPLES OF THE UNDERDRAIN BEDDING MATERIAL. TESTING LABORATORY.
- PERFORM A SIEVE ANALYSIS CONFORMING TO ASTM C136 (STANDARD TEST METHOD FOR SIEVE ANALYSIS OF FINE AND COARSE AGGREGATES 1996A) ON EACH TYPE OF THE SAMPLE MATERIAL.


TYPICAL UNDERDRAINED SOIL FILTER






/ LOAM AND SEED DISTURBED AREAS SLOPES OF 3:1 OR STEEPER LINE WITH 4" COMPACTED LOAM AND











\\nserver\CFS\Ben Grover\Village Center Estates Phase 2\Acad\Plans\DETAILS.dwg, 12/15/2020 1:38:07 PM,





irverICFS\Ben Grover\Village Center Estates Phase 2\Acad\Plans\BASE.dwg, 12/15/2020 1:44:43 PM, jrl